

Cover letter

Bernardo, thank you for the revised requirements of 20 August. This budgetary proposal covers the 85% to 15% case at 120 to 160 MT/day. We recommend mechanical dewatering ahead of the dryer: a screw press removes roughly 60% of the water at a fraction of the cost of evaporating it, which brings the dryer duty to about 7.3 MMBtu/hr at 140 MT/day and lets your biogas cover about 83% of it (LPG make-up on the order of US\$420/day at US\$14.50/MMBtu; about US\$2,500/day with the digester offline). The XD-96 Mk.2 drum is sized with margin for 160 MT/day and cake moisture variability; the burner is oversized to 15 MMBtu/hr for the same reason. Lines marked TBD are awaiting vendor quotes or your process data (effluent total solids, pH, chlorides, ammonia; biogas composition and pressure; site layout). A 5-gallon sample of the effluent to our Stuart, FL shop will let us confirm press performance and flight design. The attached process flow sheet is the mass and energy balance this proposal is built on.



Quote

Quote ref.	20260909-LETEK-A
Issue date	Sep 9, 2026
Expires	Nov 8, 2026
Currency	USD

Seller

Midwest Custom Engineering, Inc.
6526 S Kanner Hwy #215
Stuart, FL 34997
United States

Contact
Jason Shipley (jason@usemce.com)
+16202009109

Buyer

LETEK DCG

Contacts
Bernardo Urquiza (burquiza@letekdcg.com)

Effective date	Total discount	Total contract value
On agreement	\$0.00	\$718,822.00

Line items

Name	Quantity	Unit price	Unit discount	Net price
XD-96 Mk.2 Rotary Thermal Conditioning System	1	\$589,500.00	—	\$589,500.00
Application (sized with the MCE Dryer HMB Calculator, case LETEK_140tpd_caseA, 9 Sep 2026; PFD attached): Product: chicken manure biodigester effluent, screw-pressed to cake, 3/8" minus Incoming moisture content (to dryer): 70% (effluent 85% ahead of the press) Est bulk density: 55 lb/ft3 wet cake, 30 lb/ft3 dried Desired output MC: 15% Lb/hr in: 6,430 (140 MT/day of effluent at 85%) Lb/hr out: 2,269 (24.7 MT/day bedding) Lb of water removed: 4,161 per hour Gal of H2O removed: 499 per hour Est BTU of entire system: 7,281,000 BTU/hr (rigorous check 6,610,000) Drum inlet gas 900 F, exhaust 230 F, 24 h/day Fuel source: LPG with biogas (55% CH4) as primary; 145.77 MMBtu/day of biogas covers about 83% of the duty XD Series - Heavy Duty Direct Fired Rotary Thermal Conditioning System - Feed screw system with 5 HP motor - Co-current single pass Rotary Dehydration Drum (8' dia x 40' long). Drum to be constructed from A36 steel (see line 3 for stainless) - Heavy Duty Dryer Drop-Out Box for dry product - Airlock complete with 1.5 HP motor, drive and control devices, mild steel construction - Drum Drive mounted on a structural base complete with 30 HP motor and drive - Full tooth, mounted chain sprocket to match chain drive - Forged steel drum tracks with HD attachment points - Front trunnion base with hardened trunnion wheels mounted on a structural base - Rear trunnion base with hardened trunnion wheels and thrust wheel assembly mounted on a structural base - Front and rear water deluge nozzle for fire suppression - Inlet and discharge seals Exhaust Fan - XF-40 fan, arrangement #9F, AR 235 rotor, 60 HP TEFC 230-460V/3/60, V-belt drive, 23" inlet, vibration isolation sleeve, inspection door, drain port - Calculator: 12,934 ACFM at 230 F, 12 in WC static, 42 bhp Ducting and Transition - Ducting, transitions and elbows up to 60 lineal feet, 22" dia, A36 construction Control System and Fire Prevention - Basic Burner Management System control panel - Electrical and control instrumentation for MCE's proprietary processing equipment - Motor control cabinet for seller's equipment, 3 phase, 60 Hz, 480 V - Manual quench nozzles provided; automated fire suppression system quoted upon request - Standard 435 MOP burner and pre-piped, pre-wired valve train are replaced by the oversized dual-fuel burner on line 2 System Commissioning - 1 man-week; equipment installation instructions for buyer's installation contractors - Start-up and operator training				

Name	Quantity	Unit price	Unit discount	Net price
Dual-fuel burner upgrade, 15 MMBtu/hr, LPG + biogas	1	TBD	—	TBD
Burner oversized for this application per MCE engineering: 15 MMBtu/hr maximum with 10:1 turndown (normal fire 7.3 MMBtu/hr), sized to hold capacity if the press cake runs wetter than 70% or the plant runs 160 MT/day. - Dual-fuel: biogas (55% CH4, ~195 scfm at 2 psig) and LPG, two independent NFPA 86 gas trains with automatic changeover on gas pressure - Combustion air blower, flame safeguard integrated with the BMS panel - Replaces the standard 435 MOP burner and single valve train included in line 1 PRICE: burner vendor quote pending - to be added				
Stainless steel construction option	1	TBD	—	TBD
Recommended for digestate (ammonia, chlorides, pH to 8.2): 316L stainless drum shell and flights; 304 stainless drop-out box and ducting. Estimated equipment life 30-35 years for 316L versus 7-10 years for 3/8" A36. PRICE: material adder to be added on request (A36 base is priced on line 1; the 304 SS cyclone adder is priced on line 7)				
XB 4.9 Live Bottom Storage Hopper	1	\$48,995.00	—	\$48,995.00
Press cake surge ahead of the dryer feed screw, 2 hours at 6,430 lb/hr. XB 4.9 Live Bottom Storage Hopper with the following features: 2 - 9H312 9" diameter, RH, helicoid screw, 9' 10" long with ⅜" thick at base and 3/16" thick at tip, helicoid flighting, full pitch (6"), mounted with standard welds on 2" schedule 40 pipe, bushed and 2-hole drilled for 1-½" shafts 2 - 9H312 9" diameter, RH, helicoid screw, 9' 10" long with ⅜" thick at base and 3/16" thick at tip, helicoid flighting, full pitch (6"), mounted with standard welds on 2" schedule 40 pipe, bushed and 2-hole drilled for 1-½" shafts. 16 - ½" x 3" - Tem-U-Lac Coupling Bolts with locknuts 4 - 2" diameter Tail Shaft 1 - 9" x 1-½" Anti-Friction Tail Bearings 1 - Access Door with limit switch plate for backup 1 - Discharge Opening with flange, fitted 1 - Set Support Feet 1- Removable Auger End Plate 6 - Lexan Viewing Windows 2 - 5 HP TEFC motors 2 - HD gear reduction drives with final chain drives 1- Chain Safety Guard Approx Overall Dimensions: approx. 6' W" x 14'9"L x 11'8" H for more information see link here: https://www.midwestcustomengineering.com/xb-4-6-live-bottom-tank				

Name	Quantity	Unit price	Unit discount	Net price
HD Screw Conveyor Cake transfer from live-bottom hopper to the dryer feed screw. HD 12" Screw Conveyor 12' 0" long inside trough ends. Inclined 45° To Consist of: 1 - 12S412 12" diameter, RH, sectional screw, 11' 10" long with 3/16" thick sectional flights, ½ pitch (6' '), continuously welded on carry side, mounted on 2-½" schedule40 pipe, precision bushed and 3-hole drilled for 2" shafts to have 9-½" of bare pipe at discharge end 6 - ⅝" x 3-⅝" - Tem-U-Lac Coupling Bolts with locknuts 1 - 2" diameter Tail Shaft for Shelf Type Trough End, 3-hole drilled 1 - 12" x 2" Trough End with Seal and SCM Ball Bearing 1 - 12" x 2" Standard Drive Trough End with Feet prepared for screw conveyor drive 1 - 12" x 10 GA Tubular Trough 12' 0" long 2 - Black Sponge Rubber Flange Gaskets 2 - 13" x 13" x 3/16" thick Inlet Spout with Flange, fitted 2 - TE/Flange Assembly Bolt Kits BALDOR / NORD DRIVE EQUIPMENT: Baldor 3 H.P., 1,755 RPM, 3PH, 60 HZ, 230/460 volt, NORD Clincher C-Face Reducer, 172 RPM output speed, complete with 2" diameter Drive Shaft and Screw Conveyor Drive Adaptor	1	\$15,492.00	—	\$15,492.00
HE-74 Cyclone Dryer exhaust collector, 12,934 ACFM at 230 F (rated to 30,500 CFM). New HE-74 Cyclone, 10 ga, mild steel rated up to 30,500 CFM High Efficiency Centrifugal Collector Model HE-74 • CW inlet rotation • 10 gauge mild steel construction • Exterior welds continuous where possible and cleaned free of weld slag and splatter • 74" Diameter flanged collector housing with riser tube • Flanged 75° cone, welded to expansion chamber • Product discharge is flanged 10" round • Flanged rectangular inlet, 45.0" x 19.0" • Draw-thru fitting mounted on riser tube flange, 37.0" x 24.0" exhaust size • Standard mount pads • 8" Dia. bolted inspection port, F/G white sponge gasket • Housing flange gasketing to be Food Grade silicone caulking • Airstream Temperature: 70°F • painted RAL #7012 Basalt Grey • If stand with 40" clearance is desired, please add \$6,500 • If insulated with 1" insulation and aluminum cladding please add \$9,995 • If 304 Stainless Construction, please add \$21,000	1	\$30,940.00	—	\$30,940.00
HE-74 Cyclone - 304 stainless construction adder 304 stainless construction of the HE-74 for the wet, ammonia-laden dryer exhaust (adder per HE-74 catalog description). 1" insulation and aluminum cladding available for an additional \$9,995.	1	\$21,000.00	—	\$21,000.00

Name	Quantity	Unit price	Unit discount	Net price
FT-12 Airlock Rotary airlock under the HE-74 cyclone discharge; fines rejoin the dried product. FT-12 AIRLOCK COMPLETE WITH THE FOLLOWING FEATURES DROP THRU ROTARY AIRLOCK FEEDER COMPLETE WITH CAST IRON HOUSING AND END PLATES, 8-VANE OPEN END MILD STEEL BEVELED ROTOR. HEAVY DUTY DROP THRU ROTARY AIRLOCK FEEDER COMPLETE WITH CAST IRON HOUSING AND END PLATES, 8-VANE OPEN END MILD STEEL BEVELED ROTOR, OUTBOARD BEARINGS WITH THREE MOLYURETHANE U-CUP PACKING RINGS PER SIDE. COMPLETE DRIVE PACKAGE INCLUDES 1-1/2 HP 3PH 230/460 VOLT 60 CYCLE TEFC GEARMOTOR 18 RPM	1	\$12,895.00	—	\$12,895.00
OPTION: Automation and Controls (PLC / HMI upgrade) Optional upgrade in place of the basic BMS panel. Not included in the total below. Upgraded Automation and Controls - includes PLC programming of all infeed, outfeed, and product conveyance into through, and out of system includes modulation programming for burner management system (BMS) - 21.5" HMI display with modeled equipment interface includes data logging for temperatures and hours of components - includes on site programming for 1 man weeks, additional costs billed at \$1,350/day plus expenses - includes visualization programming - includes reports via emailed pdf's in customer chosen frequency - Mobile data access	1	\$89,950.00	—	\$89,950.00
Screw press dewatering system Screw press, 12,900 lb/hr (5.8 m3/h) of digestate at 15% TS to 30% TS cake, 316 SS screen and screw, with agitated receiving tank (8 h) and progressive-cavity feed pump. Cake moisture sets the dryer duty; a bench test on a 5-gallon sample is required. PRICE: vendor quote pending - to be added	1	TBD	—	TBD
Biogas conditioning skid For 195 scfm (7,455 Nm3/day): iron-oxide H2S vessel (5,000 ppm in, under 200 ppm out), chiller / coalescer moisture knockout, booster blower to 2 psig, flame arrester, pressure control. PRICE: allowance to be added once the biogas analysis (H2S, moisture, supply pressure) is received	1	TBD	—	TBD
Freight FOB Stuart, FL. Sea freight door to door Stuart - Miami - Progreso - Merida estimated at \$27,206 in April 2026 (two 40 ft HiCube containers plus one oversize drum piece); to be re-quoted for the XD-96 and billed at time of shipment.	1	TBD	—	not included
Subtotal				\$718,822.00
Discount included in the subtotal				\$0.00
Total contract value				\$718,822.00

Terms

50% down with order, 30% on approval drawings, 15% before shipment, 5% on start-up. Budgetary proposal, valid 60 days. Delivery 18-22 weeks after approval drawings, to be confirmed by production at time of order. Installation, foundations, utilities, permits, biogas and LPG supply, effluent storage and pressate disposal by others. Prices in US dollars, FOB Stuart, FL, exclusive of taxes and duties.

Acceptance

This section is designated for the authorized representatives from both parties involved in this agreement. By signing below, the signatories confirm their acceptance of the terms and conditions outlined in this document.

Signature

Date

Printed name

Questions? Contact me

Jason Shipley
jason@usemce.com
+16202009109

Midwest Custom Engineering, Inc.
6526 S Kanner Hwy #215
Stuart, FL 34997
United States

LETEK DCG / Bachoco - chicken manure

DEHYDRATION SYSTEM MASS-ENERGY BALANCE

3.22 TPH wet chicken manure digestate cake (screw-pressed)
 4.33 C.Y./hr @ 1485 lb/C.Y. and 70% moisture
 8x40 Single-pass rotary drum · XD-96 (8'x40')
 Elevation 30 feet (above sea level)

Fuel to Burner	
Propane	
19,900 Btu/lb	
366 lb/hr	
7.28 MMBtu/hr	

Make-Up Air	
5,704 SCFM	
85 deg F	

Mixed Inlet Gases	
7,445 SCFM	
900 deg F	

Combustion Air	
1,675 ACFM	
85 deg F	
30% X-S air	

Wet Feed	
70.0% moisture	
1,929 lb/hr solids	
4,501 lb/hr water	
6,430 lb/hr total	

1,589 Btu's/lb evaporation (rigorous)



EVAPORATION RATE
 4,161 LB/HR H2O


XD-96 (8'x40') · 40 ft long · 8.7 MMBtu/hr burner

Dry Fuel (product burned)	
0 lb/hr total	

Net Dry Product	
2,269 lb/hr total	

Exhaust Gases	
12,934 ACFM	
50 hp fan	

Dryer Outlet Gases	
12,934 ACFM	
230 deg F	



Dry Material	
15.0% moisture	
1,929 lb/hr solids	
340 lb/hr water	
2,269 lb/hr total	
180 deg F	

