
LETEK DCG / Bachoco - digestat

DEHYDRATION SYSTEM MASS-ENERGY BALANCE

1.58	TPH wet chicken manure digestate cake (screw pres
2.12	C.Y./hr @ 1485 lb/C.Y. and 70% moisture
6x30	Single-pass rotary drum · XD-72 (6'×30')
Elevation	30	feet (above sea level)



1,589 Btu's/lb evaporation (rigorous)

Exhaust Gases	
6,342	ACFM
25	hp fan


Dryer Outlet Gases	
6,342	ACFM
230	deg F

Fuel to Burner	
Propane	
19,900	Btu/lb
179	lb/hr
3.57	MMBtu/hr

Make-Up Air	
2,797	SCFM
85	deg F

Mixed Inlet Gases	
3,651	SCFM
900	deg F





Wet Feed	
70.0%	moisture
946	lb/hr solids
2,207	lb/hr water
3,153	lb/hr total

Combustion Air	
821	ACFM
85	deg F
30%	X-S air

EVAPORATION RATE

2,040 LB/HR H2O

XD-72 (6'×30') · 30 ft long · 4.3 MMBtu/hr burner

Dry Fuel (product burned)	
0	lb/hr total

Net Dry Product	
1,113	lb/hr total

Dry Material	
15.0%	moisture
946	lb/hr solids
167	lb/hr water
1,113	lb/hr total
180	deg F

MIDWEST CUSTOM ENGINEERING
PRECISION QUALITY INTEGRITY