



Small Pack Expansion - FRMco

Farmer's Rice Milling

3211 Highway 397
Lake Charles, LA 70615
United States

Mark Suiter
msuiter@frmco.com
+19014637118

Reference: 20260113-124701306
Quote created: January 13, 2026
Quote expires: April 13, 2026
Quote created by: Jason Shipley

jason@usemce.com
+16202009109

Comments from Jason Shipley

Per your request we are pleased to provide the quotation on the following small pack expansion line:

Products & Services

Item & Description	Quantity	Unit Price	Total
Transitions Supply and Purge Chute Transition	11	\$750.00	\$8,250.00
12" x 12" Gate 12" x 12" gate All electric & air gates have safety covers included in electric & air add-on pricing. The electric add-on pricing includes high density plastic rollers as a standard feature for standard ceiling gates. Actuator drive gates travel approximately 2.8 inches per second. Gear head drive gates less than 24" travel 3.0 inches per second and gates 24" and larger travel 1.8 inches per second. 24 Volt Solenoids Available. Consult Factory	8	\$3,785.00	\$30,280.00

Item & Description	Quantity	Unit Price	Total
39' Drag Conveyor - 44' - 9X9 GALV. LEVEL DRAG - CLASS II - TORQUE ARM II - SHAFT MOUNT REDUCER, SF 2 - 2HP, 1800 RPM, 230/460V/3/60, 145T, TEFC - (44) 9X9 1/4" AR STEEL LINING - BOTTOM - (44) 9X9 10GA AR STEEL LINING- SIDES - 9X9, 9X17 TOP INLET - 9X9 HEAD DISCHARGE TRANSITION - (44) 9X9 RETURN RAILS - (36) STEEL CARRY OVER RETURN CUP - (9) 81XH CHAIN ADDER WITH WELDMENTS 10' - (2) 9X9,9X17,9X14 RAISED INSPECTION DOOR KIT - (3) 9" INTERMEDIATE RACK & PINION CROSS SLIDE GATE - (3) ELEC R&P 1/3HP 230/460V/3 60HZ	1	\$34,796.94	\$34,796.94
Storage Bins Heavy-duty, storage bin designed for use in feed, grain, biomass, and ingredient processing environments. The unit includes a fully welded upper wall assembly, converging lower hopper section, access door with viewing window, and reinforced leg structure for stable floor mounting. Approximate Overall Dimensions: Height: ~245 in (20.4 ft) Width: ~120 in Depth: ~120 in Standard Features: - 1/4" A36 mild steel hopper - 12 ga A36 mild steel upper side wall - Reinforced structural frame and legs - Plexiglass Indicator Panel - 2x Access doors for inspection - Top cover - Suitable for dry bulk materials	3	\$58,500.00	\$175,500.00
J-System Fumigation for bins	3	\$3,900.00	\$11,700.00

Item & Description	Quantity	Unit Price	Total
XF-19 Fan	3	\$7,950.00	\$23,850.00
Exhaust Fan			
· XF-19 Fan			
· Arrangement #9F heavy-gauge steel base with continuous welds.			
· Heavy-duty pillow block bearings.			
· Turned, ground, and straightened shaft.			
· Dynamically and statically balanced rotor with tapered hub and bushing.			
· Narrow width high static, heavy-duty rotor.			
· Rotor to be fabricated of AR 235 Plate Steel.			
· Heavy duty housing with continuous welds.			
· Housing to be fabricated of carbon steel.			
· Motor slide base with integral drive tensioning mechanism.			
· 10 HP, 1800 RPM, class TEFC, 230-460V/3/60 NEMA Premium efficient motor.			
· NOTE: TEFC motor with no environmental marking/T Code.			
· V-belt drive with 1.5 to 2.0 service factor.			
· Totally enclosed sanitary belt and shaft guard.			
· Factory test run prior to shipment.			
· Inlet to 11" OD.			
· Flanged rectangular outlet.			
· Housing to have a drain port in the bottom.			
· Product contact zones unpainted, all other surfaces painted Basalt Gray; guards painted safety orange. Please specify otherwise.			

Item & Description	Quantity	Unit Price	Total
Dust Control Filter - FILTER TO HANDLE 2,000 CFM OF RICE DUST AT 70°F - FILTER STRESSED TO 17" W.G. - FLANGED CONSTRUCTION - SIDE BAG REMOVAL - HINGED SERVICE DOOR - NEMA 4 ENCLOSURE - STEEL PLATED VENTURI & CUP - STAINLESS STEEL BAG CLAMPS - 16 OZ. SINGED POLYESTER BOTTOM REMOVAL BAGS - GALVANIZED CAGES - MAGNEHELIC GAUGE KIT - 4X4 SAFETY GRATE - EXTERIOR PRIMED & PAINTED AIRLANCO WHITE - SAFETY EQUIPMENT PAINTED SAFETY YELLOW NOTE: A 110 VOLT SINGLE PHASE ELECTRICAL SOURCE IS REQUIRED FOR THE TIMER BOX. A COMPRESSED AIR SOURCE OF 4.43 SCFM AT 80-100 PSI IS REQUIRED FOR MEDIA CLEANING.	3	\$21,296.25	\$63,888.75
BIN LEVEL SENSOR - Solido 115V - Install level sensor (Hi/Lo) - Includes mounting couplings and protective baffles installed in the hopper. - Customer to wire the level sensor to product feeding equipment to control the high and low level of product. - Rotating Paddle Switch 115 VAC 50/60Hz	14	\$455.00	\$6,370.00
Est Ductwork Estimated ductwork - final sizing, diameter, and gauge TBD upon site plan layout. - Estimate for duct piping on second floor.	1	\$9,233.00	\$9,233.00
28' Belt Conveyor - 12" - 28' OAL INCLINE BELT CONVEYOR - FULLY ENCLOSED - POWDERCOATED - DRIVE KIT AND MOTOR MOUNT	1	\$16,899.61	\$16,899.61

Item & Description	Quantity	Unit Price	Total
24' Elevator Leg - 26' DH. 9" D. 6X4 -5" SPACING ELEVATOR - CLASS II - TORQUE ARM II - SHAFT MOUNT REDUCER, SF 2 - 1.5HP - 1800 RPM - 230/460V/3/60 - 145T - TEFC - 9" 6X4 SINGLE FEED BOOT HOPPER	1	\$11,123.08	\$11,123.08
Plate Magnet Hinged plate magnet for installation in Gentle Handler elevator leg inlet transition	1	\$2,490.00	\$2,490.00
60' Drag Conveyor - 60' - 9X9 GALV. LEVEL DRAG - CLASS II - TORQUE ARM II - SHAFT MOUNT REDUCER, SF 2 - 5HP, 1800 RPM, 230/460V/3/60, 145T, TEFC - (60) 9X9 1/4" AR STEEL LINING - BOTTOM - (60) 9X9 10GA AR STEEL LINING- SIDES - 9X9, 9X17 TOP INLET - (2) ELEC R&P 1/3HP 230/460V/3 60HZ - (60) 9X9 RETURN RAILS - (2) 9X9, 9X17, 9X14 RAISED INSPECTION DOOR KIT - (2) 9" INTERMEDIATE RACK & PINION CROSS SLIDE GATE - CARRY BACK CUPS Note: This is not exact measurement of conveyor; exact measurements are being recorded prior to ordering equipment	1	\$37,732.20	\$37,732.20
Three-Way Valve 8" THREE-WAY VALVE - Pan type - 10 Gauge - For two heavy duty 1/3 h.p. Duff Norton actuators - Totally enclosed - 230-460 volt - Three phase	1	\$6,508.75	\$6,508.75

Item & Description	Quantity	Unit Price	Total
Two-Way Valve - 8" TWO-WAY VALVE - Y-Style - Pan Type - For heavy duty 1/3 h.p. Duff Norton actuator - Totally enclosed - 230-460 volt - Three phase	1	\$4,097.50	\$4,097.50
One-time subtotal			\$442,719.83
Total			\$442,719.83

Purchase terms

50% down on receipt, balance on shipment.

Signature

Signature

Date

Printed name

Questions? Contact me



Jason Shipley
jason@usemce.com
+16202009109

Midwest Custom Engineering, Inc.
6526 S Kanner Hwy #215
Stuart, FL 34997
United States