

## Cover letter

Midwest Custom Engineering (MCE) is pleased to quote the design, manufacture, installation and commissioning of a turnkey system that breaks down large round or large square bales of hay, haylage and straw and re-packs the material into small, accurately weighed, compressed poly-bag packs. This budgetary proposal covers a complete turnkey line engineered specifically to your requirements.

## Executive summary

Performance Basis

Parameter    Design Target

Feedstock    Large round & large square bales — hay, haylage, straw (haylage ~35% moisture)

Output pack    Compressed poly-bag pack, nominal 600 × 400 × 220 mm, from ~20 kg

Throughput    ~80 packs/hr (1 operator); up to ~180 packs/hr (two operators / favorable material)

Weigh accuracy    ± 0.1 kg (independent weigh conveyor)

Dust removal    > 95% of dust and mold spores

Controls / safety    PLC + HMI; guarding & safety circuit to OSHA / ANSI B11 / ISO 13849 intent; UL 508A panel



## Quote

|            |                    |
|------------|--------------------|
| Quote ref. | 20260730-114551866 |
| Issue date | Jul 30, 2026       |
| Expires    | Oct 28, 2026       |
| Currency   | USD                |

## Seller

**Midwest Custom Engineering, Inc.**

6526 S Kanner Hwy #215

Stuart, FL 34997

United States

### Contact

Jason Shipley (jason@usemce.com)

+16202009109

## Buyer

**Re-Covr LLC**

1718 Capitol Ave

Cheyenne, WY 82001

### Contacts

Dusty Allison (dusty@pacwestglobal.net)

| Effective date | Total discount | Total contract value |
|----------------|----------------|----------------------|
| On agreement   | \$0.00         | \$895,000.00         |

## Line items

| Name            | Quantity | Unit price   | Unit discount | Net price    |
|-----------------|----------|--------------|---------------|--------------|
| Scope of Supply | 1        | \$895,000.00 | —             | \$895,000.00 |

MCE will supply the following ten integrated subsystems as a single turnkey line:

Subsystem: Function

1. Walking-floor infeed: Slat-floor deck (holds 4–6 large bales) that meters bales into the breaker; hydraulically driven.
2. Bale breaker / doffer: Spiked conveyor and doffing comb break and thin the forage to a uniform, weighable flow.
3. Dust extraction: Cyclone, fan, ducting and airlock removing >95% of dust and mold spores.
4. High-accuracy weigh conveyor: Independent load-cell weigh belt calibrated to 0.1 kg.
5. Compression press + bag-fill: Hydraulic press compacting each weighed charge into a poly bag (~600 × 400 × 220 mm).
6. Twin heat-seal station: Twin-seal heat sealer that closes and secures each filled bag.
7. Outfeed conveyor: Take-away and accumulation of finished packs.
8. Hydraulic power unit High-efficiency HPU (~20–30 hp) driving the press, floor and breaker.
9. Controls & automation: PLC/HMI, UL 508A panel, VFDs, sensors, safety-rated circuit.
10. Structure, guarding & finish: Structural frame, stainless-steel contact surfaces, guarding and safety devices.

Performance Basis

Parameter    Design Target

Feedstock    Large round & large square bales — hay, haylage, straw (haylage ~35% moisture)

Output pack    Compressed poly-bag pack, nominal 600 × 400 × 220 mm, from ~20 kg

Throughput    ~80 packs/hr (1 operator); up to ~180 packs/hr (two operators / favorable material)

Weigh accuracy    ± 0.1 kg (independent weigh conveyor)

Dust removal    > 95% of dust and mold spores

Controls / safety    PLC + HMI; guarding & safety circuit to OSHA / ANSI B11 / ISO 13849 intent; UL 508A panel

Lead time: Approximately 9–12 months from receipt of order and approved requirements, for this first-of-kind turnkey system.

Warranty: 12 months on MCE workmanship from site acceptance; bought-in components carry their respective OEM warranties.

Support: Installation, commissioning and operator hand-off included; ongoing service and spare-parts support available under separate agreement.

Exclusions

Unless added by written scope change, this quotation excludes:

- Site civil works, foundations and building modifications.
- External material-handling equipment (loaders, telehandlers) to feed the infeed.
- Bag / film consumables and dust-collection waste disposal.
- Spare-parts inventory beyond commissioning spares.
- Freight and rigging beyond the installation allowance; applicable sales/use taxes.
- CE marking and EU / non-U.S. regulatory compliance.

Terms & Basis of Quotation

- This quotation is valid for 60 days from the date of issue.
- Pricing is based on the outline specification and scope stated herein; a firm fixed price will be confirmed following a joint requirements sign-off. Material pricing is subject to steel and component market movement at time

| Name | Quantity | Unit price | Unit discount | Net price |
|------|----------|------------|---------------|-----------|
|------|----------|------------|---------------|-----------|

of order.

- Title passes on final payment; risk passes on delivery to site. Standard MCE terms and conditions of sale apply.
- Changes to scope, specification, throughput or output pack size may affect price and lead time and will be handled by written change order.
- Taxes, duties and permits (where applicable) are for the customer's account.

Billing summary: Starts on effective date

|                 |                     |
|-----------------|---------------------|
| <b>Subtotal</b> | <b>\$895,000.00</b> |
|-----------------|---------------------|

|                                   |        |
|-----------------------------------|--------|
| Discount included in the subtotal | \$0.00 |
|-----------------------------------|--------|

|                              |                     |
|------------------------------|---------------------|
| <b>Due on effective date</b> | <b>\$895,000.00</b> |
|------------------------------|---------------------|

The total amount due on the effective date, not including any future payments due later.

|                             |                     |
|-----------------------------|---------------------|
| <b>Total contract value</b> | <b>\$895,000.00</b> |
|-----------------------------|---------------------|

## Terms

50% down, balance before shipment

## Payments

Customer must agree to the following payment terms: due on receipt

## Acceptance

This section is designated for the authorized representatives from both parties involved in this agreement. By signing below, the signatories confirm their acceptance of the terms and conditions outlined in this document.

On behalf of the buyer,

[sig|req|signert]

**Dusty Allison**

dusty@pacwestglobal.net