

Cover letter

Please note: we are quoting without knowing required throughput, but rather from customer requested number of mills.

Executive summary

We are pleased to provide the selected components and equipment based on the following application information:

Location: TBD, South Korea

Feedstock: Woody biomass 1/4" minus, baled in 48" dia x 49" H bales

Infeed rate: 6.5 TPH max per mill (with est 50% re-run)

Incoming Moisture Content: 5%

Desired throughput: 40 TPH, 1/4" minus

Est Bulk Density: 7-11 lb/ft³

Wood Flour will require recycle system. Conveyance not quoted until layout drawing is determined. Need site information to complete.

Note: Explosion Suppression System required, quoted after layout is determined.



Quote

Quote ref.	20260730-120028634
Issue date	Jul 30, 2026
Expires	Oct 28, 2026
Currency	USD

Seller

Midwest Custom Engineering, Inc.

6526 S Kanner Hwy #215

Stuart, FL 34997

United States

Contact

Jason Shipley (jason@usemce.com)

+16202009109

Buyer

United Export Group

1718 Capitol Ave

Cheyenne, WY 82001

Contacts

Dusty Allison (dusty@pacwestglobal.net)

Effective date	Total discount	Total contract value
On agreement	\$0.00	\$1,220,558.00

Line items

Name	Quantity	Unit price	Unit discount	Net price
XM-60" SC Magnet Adapter	3	\$24,610.00	—	\$73,830.00

- Auto Self Clean 60 degree magnet chute
- Stainless steel front, stainless steel hinged magnet plate, air operated with two air cylinders and trash pans
- SF 300 60" plate Magnet
- One micro safety switch to indicate when door is open

Billing summary: Starts on effective date

XM-4460 Hammer Mill	3	\$112,538.00	—	\$337,614.00
----------------------------	---	--------------	---	--------------

New Model: XM-4460 Hammer Mill - Extra Heavy Duty Mill Design

Direct Drive, Dual Grinding Chamber, Gravity Discharge Hammer Mill

- w/ motor base extension
- Reversible top feed inlet
- Screen Carriage
- Screen Size/Type: #4 (1/16")
- Two (4 total) sets of screens
- Construction: Mild Steel with AR liners
- 7080 sq in screen area
- Hammer Type: hard faced, heat treated
- One (1) set hard faced hammers included
- HP Range: 300-600 HP
- Operating Horsepower: 437 HP
- Motor Quoted: 450 HP, 1800 RPM, 3/60/ 230-460V, TEFC Premium Efficiency, Totally Enclosed Fan Cooled, 1.15 SF (quoted below)
- Included Features: Top feed inlet, Mill/Motor, Support base, 3 Nema 4/12 Limit Switches and OSHA guard.
- with Vibration Switch & Rubber Vibration Pads

Billing summary: Starts on effective date

450 TEFC Motor - 1800 RPM	3	\$32,249.00	—	\$96,747.00
----------------------------------	---	-------------	---	-------------

Motor

450 HP

1800 RPM

460V

L449T Frame

Rigid Base

Insulated ODE Bearing

Billing summary: Starts on effective date

Custom Plenum Chamber	3	\$48,995.00	—	\$146,985.00
------------------------------	---	-------------	---	--------------

Custom Plenum chamber with structure

- includes mounting plate for hammer mill
- includes support structure for hammer mill - 24" clearance under airlock

Name	Quantity	Unit price	Unit discount	Net price
• with mounting plate for dust filter or ducting flange as req'd • with stairs or ladder and gate as required per site location				
Billing summary: Starts on effective date				
Plenum Manwalk Access	3	\$7,995.00	—	\$23,985.00
Custom Platform to provide access for each side of mill - Grip strut walkway - with toe kicks - with hand rail - with safety gate				
Billing summary: Starts on effective date				
4460 Dust Control Filter	3	\$65,140.00	—	\$195,420.00
81AST 10 STYLE II DUST CONTROL FILTER WITH 1,328 SQ. FT. OF CLOTH INCLUDING THE FOLLOWING FEATURES: FILTER TO HANDLE 9360 CFM OF GRINDING CORN DUST AT 70°F FILTER STRESSED TO 17" W.G. FLANGED CONSTRUCTION TOP BAG REMOVAL LIFT OFF STYLE TOP SERVICE DOORS 16 OZ. D/P SNAP BAND TOP REMOVAL BAGS NO TOOL GALVANIZED CAGES NEMA 4 ENCLOSURE MAGNEHELIC GAUGE KIT EXPLOSION VENT MOUNTED IN SPECIAL HOUSING SECTION BELOW BAGS LADDER, CAGE, TOP GUARDRAIL, AND SAFETY GATE EXTERIOR PRIMED & PAINTED WHITE SAFETY EQUIPMENT PAINTED SAFETY YELLOW NOTE: A 110 VOLT SINGLE PHASE ELECTRICAL SOURCE IS REQUIRED FOR THE TIMER BOX. A COMPRESSED AIR SOURCE OF 17.95 SCFM AT 80-100 PSI IS REQUIRED FOR MEDIA CLEANING.				
Billing summary: Starts on effective date				
Transfer Screw Conveyor - 4460	3	\$29,875.00	—	\$89,625.00
Qty (1) - 18" diameter Screw Conveyor 21' 0" Long inside trough ends, to convey 10 TPH (2857 CFH) of ground corn at 8 PCF, control fed at 45% trough loading, at 46RPM. Horizontal				
Unit is to consist of: 1 - 18" diameter RH Sectional screw, 20' 8" long. Starting at the feed end, the first 20' 0.5" is to have 1/4" thick sectional flights, full pitch (18"), Standard welds; the last 0' 7.5" is to have bare pipe at the discharge end. All flights are to be mounted on 6" Schedule 40 pipe, bushed and 3-hole drilled to accept 3-7/16" diameter shafts				

Name	Quantity	Unit price	Unit discount	Net price
6 - 7/8" x 8" - Tem-U-Lac Coupling Bolts with locknuts				
1 - 3-7/16" diameter Tail Shaft, 3-hole drilled				
1 - 18" x 3-7/16" Anti-Friction Tail Trough End with WPS & Lip Seal; trough end is to be designed for use with flared troughs				
1 - 18" x 3-7/16" Standard Drive Trough End with Feet prepared for screw conveyor drive; trough end to act as 4th side of flush end discharge				
1 - 18" x 3/16" thick Flared Trough 18' 0" long; trough to be uncovered to act as inlet				
1 - Flared to U-Trough Adaptor Plate				
1 - 18" x 3/16" thick Single Flanged Trough 3' 0" long				
1 - 18" x 12 GA Flanged Cover(s) 3' 1-1/2" long, with black sponge rubber gasketing and bolted for covers on 12" centers				
4 - Black Sponge Rubber Flange Gaskets				
1 - 19" x 19" x 3/16" thick flush end discharge spout, fitted				
4 - TE/Flange Assembly Bolt kit				
2 - 18" Support Feet				
1 - 18" x 3/16" thick x 36" long Shroud, fitted				
1 - Set of General Arrangement Drawings for Customer Approval prior to construction and fabrication				

NOTE: Exterior only to have (1) shop coat standard Grey enamel paint.

DRIVE EQUIPMENT: Baldor 10 HP., 1750 RPM., 3PH., 60 HZ., 230/460 volt, TEFC motor with a 215 T-frame, motor mounted at 12 o'clock position. Dodge TA4207H25 taper bushed reducer, class 2 gearing, 46 RPM output speed, complete with 3-7/16" diameter drive shaft, motor mount, SCD adaptor, sheaves, adjustable packing kit, (2) v-belts, and belt guard.

Billing summary: Starts on effective date

Fan for 4460 Mill	3	\$12,964.00	—	\$38,892.00
--------------------------	----------	--------------------	----------	--------------------

Fan for XM-4460 Hammer Mill Dust Control Filter

Type: BIHS

Size: 182

Width: 100 %

Speed: 3,494 RPM

Max Design Speed: 4,081 RPM

Volume: 9,204 Acfm

Fan Static Pressure: 12.0 in.wg.

Fan Inlet Air Density: 0.0715 lb/ft³

Inlet Pressure: -12.0 in.wg.

Outlet Velocity: 4,936 fpm

Operating Temp: 68 °F

Elevation: 500 ft ASL

Fan Shaft Power: 24.0 hp

Cold Start Power (68°F): 24.0 hp

Static Efficiency: 70 %

FEI: 1.29

Sound Data

Noise Level based on hemispherical

Name	Quantity	Unit price	Unit discount	Net price
free field conditions (Q=2) Measurement Distance = 5 ft Octave Band Lw dB Lp dB 63 Hz 102 91 125 Hz 99 88 250 Hz 97 85 500 Hz 102 90 1000 Hz 94 82 2000 Hz 93 81 4000 Hz 88 77 8000 Hz 84 72 Overall Predicted Noise Level = 90 dBA Open Inlet 8905@ 12" - Performance Billing summary: Starts on effective date				

Explosion Vent - 44"	6	\$4,585.00	—	\$27,510.00
44" x 44" (1130x1130mm) Domed Explosion Vent Panel with EPDM Gasket (EV-VD). Certified: ATEX II GD, EN 14491, EN 14994, EN 14797, EN 1127.1 Certificate #: INERIS15ATEX0001 - Quality Assurance Notification #: INERIS 08ATEXQ406. Relief Area: 5.7695 Billing summary: Starts on effective date				

8'x24' Rotary Trommel System	1	\$189,950.00	—	\$189,950.00
8'x24' Rotary Trommel System • Infeed Chute • Dual Screen Rotary Screening Drum (8' dia x 24' long). Drum screens to be constructed of 10 ga A36 Mild Steel Construction, screen size est 40 mesh. • Dual collection hoppers for sized product, A36 construction. • Discharge Guard with integral dropout shield for overs product collection, A36 construction. • Trommel Drive Complete with motor and drive. • Channel Iron Drum Tracks with HD attachment points • Front Trunnion Base With Heat Treated Wheels and industrial pillow block bearings. • Front Trunnion Base with Heat Treated Wheels and industrial pillow block bearings. Billing summary: Starts on effective date				

Subtotal **\$1,220,558.00**

Discount included in the subtotal **\$0.00**

Due on effective date **\$1,220,558.00**

The total amount due on the effective date, not including any future payments due later.

Terms

50% down, balance before shipment

Payments

Customer must agree to the following payment terms: due on receipt

Acceptance

This section is designated for the authorized representatives from both parties involved in this agreement. By signing below, the signatories confirm their acceptance of the terms and conditions outlined in this document.

On behalf of the buyer,

[sig|req|signer1]

Dusty Allison

dusty@pacwestglobal.net